



WINDOWS	
600X1200	0
900X1200	2
400X500 OBSCURE	0
BURGLAR BAR	YES
BLINDS	YES
DOORS	
SGL EXTERIOR	0
DBL EXTERIOR	0
INTERNAL	0
SECURITY GATE	0
CYLINDER LOCK	0
BATHROOM	
TOILET	0
URINAL	0
SHOWER	0
BASIN	0
GEYSER 150L	0
KITCHEN	
SINK UNIT 900	0
BASE UNIT 900	0
WALL UNIT 900	0
WORKTOP	0
ELECTRICAL	
D.B (SINGLE PHASE)	1
SGL FLUOR. LIGHT	2
DBL FLUOR. LIGHT	0
OUTSIDE LIGHTS	2
SGL LIGHT SWITCH	0
DBL LIGHT SWITCH	1
DAYLIGHT SWITCH	0
AC SPLIT 9000BTU	0
AC SPLIT 12000BTU	1
SOCKETS	
SINGLE 16 AMP	0
DOUBLE 16 AMP	3
A/C POINTS	1
GEYSER POINTS	0
STOVE POINTS	0
OTHER	
STEEL CHASSIS	YES
VINYL FLOOR	YES
JACKS AND SLABS	6
STEPS	1



Team Engineers (Pty) Ltd
Tel: (+267) 390 2520
E-mail: info@team-botswana.com

CLIENT: **RENTAL**

DRAWING No.: **0603-OP (STANDARD 2020)**

DESIGN: S.MMOLAI
DATE: 12/01/2021

CHECKED: SMMOLAI
DATE: 21/01/2022

APPROVED:

DATE:

CHASSIS No.: 0000

SCALE: 1:30

SIZE: A4

SHEET:

PROJECT DESCRIPTION: FLOOR PLAN
6 X 3M MOBILE UNIT-STANDARD OPEN PLAN

REV NO:

00

REVISION COMMENTS:

NOTES:

- UNLESS STATED OTHERWISE, ALL LINEAR MEASUREMENTS ARE IN MM AND ANGULAR MEASUREMENTS ARE IN DEGREES.
- BOTH INTERNAL & EXTERNAL WALLS ARE MADE OF 60MM THICK CHROMADEK PANELS.